

SITC of 5 KWp ON GRID SOLAR POWER PLANT AT SBBJ
JN SRIGANGANAGAR, BRANCH

TENDER DOCUMENT

STATE BANK OF BIKANER AND JAIPUR
PREMISES DEPARTMENT, HEAD OFFICE
TILAK MARG, JAIPUR – 302005
0141-5101545

Brief Details of the Tender

Earnest Money Deposit (EMD)	:	Rs. 8000/- (Rupees Eight thousand only) in the form of Demand Draft in favor of State Bank of Bikaner and Jaipur payable at Jaipur (EMD should be submitted in separate sealed envelope super scribing the name)
Validity of Tender	:	90 Days from the date of opening of tender.
Last Date of submission of Sealed Tender	:	23.03.2016 up to 2:00 PM
Dated of Opening of Tender	:	23.03.2016 at 4:00 PM or as intimated
Period of Completion	:	One Month
Defects Liability Period	:	12 (Twelve) Months from the date of Virtual Completion
Agreed Liquidated Damages	:	a) 1.0% of the contract value for each week of delay. Subject to maximum of 10% of the contract value.
Estimated cost of work	:	Rs. 4.00 lakhs.(Rupees Four Lakhs Only)
Cost of Tender	:	Rs. 1000/- (One thousand only)

The Bank is not bound to accept the lowest tender/ offer/ quotation and reserve the right accept or reject any or all the tenders/ quotations without assigning any reasons whatsoever.

STATE BANK OF BIKANER AND JAIPUR
PREMISES DEPARTMENT, H.O. JAIPUR

Date: 02.03.2016

Dear Sir/s,

SITC of 5 KWp ON GRID SOLAR POWER PLANTS AT SBBJ JN
SRIGANGANAGAR BRANCH

NOTICE OF INVITATION TO TENDER

Sealed tenders on item rate basis are invited from the competent enlisted **CONTRACTORS** in the appropriate category with SBBJ/ RRECL/MNRE/ ANY Public sector UNIT/Any Govt. Organization and who have worked for installation of solar power plants of similar nature and magnitude in various having sound technical and financial capacity for the aforesaid work. The proof of the similar works from the concerned organization/self certification must be submitted along-with the tender, which may be verified later by the Bank. Tender document may be downloaded from Bank's web-site (<http://www.sbbjbank.com>) as well as Govt's web-site (<http://www.tenders.gov.in>) and can also be obtained from the office of the undersigned. While submitting tender, a crossed Demand Draft of Rs. **1000/-** (One Thousand only) (Non – refundable) is to be enclosed against cost of the tender in the favor of AGM (Premises), SBBJ HO Jaipur.

Estimated cost of the Work	:	Rs. 4.00 lakhs.
Earnest Money	:	Rs. 8000/- (Rupees Eight Thousand only) in the form of Demand Draft in favour of State Bank of Bikaner and Jaipur payable at Jaipur
Place where tenders to be submitted	:	The Assistant General Manager, Premises, State Bank of Bikaner & Jaipur, Head Office, Tilak Marg, Jaipur – 302005.
Time and date of submission of Tender	:	Upto 2.00 P.M. on 23.03.2016
Time and date of opening of tenders	:	4.00 PM on 23.03.2016 or as intimated

**The Assistant General Manager,
Premises.**

स्टेट बैंक ऑफ बीकानेर एण्ड जयपुर
परिसर विभाग, प्रधान कार्यालय, जयपुर

5 KWp सोलर पावर पैक की आपूर्ति व स्थापना हेतु

उक्त कार्य करने हेतु **उपयुक्त** टेकेदारों से मोहरबंद निविदा आमंत्रित की जाती है। कृपया संबंधी प्रमाण पत्र संलग्न करें।

निविदा का विवरण हमारे बैंक के वैबसाइट (<http://www.sbbjbank.com>) अथवा सरकार के वैबसाइट (<http://www.tenders.gov.in>) से ली जा सकती है। निविदा भरत समय टेंडर के साथ रू. 1000/- का डिमांड ड्राफ्ट लगानी है।

1. अनुमानित लागत : रू.4.00 लाख
2. धरोहर राशि : रू. 8000/-
3. निविदा जहाँ डाली जानी है : परिसर विभाग, प्रधान कार्यालय, जयपुर
4. निविदा डालने की अंतिम तिथि: 23.03.2016 अपराह्न 2.00 बजे तक
5. निविदा खोलने की तिथि : 23.03.32016 अपराह्न 4.00 बजे
6. कार्य पूर्ण करने का समय : 1 माह

सहायक महाप्रबंधक (परिसर)

GENERAL RULES AND INSTRUCTIONS FOR THE GUIDANCE OF TENDERERS

1. Tenders are hereby invited on behalf of State Bank of Bikaner & Jaipur, Jaipur for PROPOSED Installation of **5 KWp On grid SOLAR POWER PLANT AT SBBJ JN SRIGANGANAGAR SBBJ BRANCH.**
2. Contract documents consist of Pro-forma for Pre-qualification, detailed plans, technical specification, schedule of quantities of the various classes of work to be done, and the set of 'conditions of contract' to be complied with by the person whose tender may be accepted. **Tender documents may be downloaded from the Bank's web -site (<http://www.sbbjbank.com>) as well as Govt's web-site (<http://www.tenders.gov.in>) or can also be obtained from the office of the undersigned. While submitting tender, a crossed Demand Draft for Rs. 1000/- (One thousand only) (Non- refundable) is to be enclosed against cost of the tender, payable at JAIPUR during the office hours on working days. Therefore, contractors are advised to visit the site before quoting the rates.**
3. Tenders which should always be placed in two envelopes, with the name of the project written on the envelopes will should contain Earnest Money Deposit, Tender Fee, Pre-qualification forms, conditions of contract and technical specifications. Envelope-2 should contain Price bid. The decision of the committee regarding prequalification of contractors shall be final.
4. The time allowed for carrying out of the work will be 1-months day.
5. The contractors should quote in figures as well as in the words the rates and amount tendered by them. The amount for each item should be worked out and the requisite totals given. Rates quoted by the contractor in item rate tender in figures and words shall be accurately filled in so that there is no discrepancy in the rates, figures and words.

However, if a discrepancy is found in the rates, which correspond with the amount worked out by the contractor shall be taken as correct. If the contractor does not work out the amount of an item or it does not correspond with the rate written either in figure or in words then the rates quoted by the contractor in words shall be taken as correct. Where the rates quoted by the contractor in figures and in words tally but the amount is not worked out correctly the rates quoted by the contractor will be taken as correct and not the amount.

6. The tender document must be filled in English and all the entries must be made by the hand and written in ink. If any of the documents are missing or un-signed, the tender shall be considered invalid.
7. Issue of tender form will be stopped one day before the date fixed for the opening of tenders.
8. Earnest money amounting to Rs.8000/- (**Rupees Eight Thousand Only**) in the form of bank draft drawn in favor of State Bank of Bikaner and Jaipur, must accompany with each tender and each tender is to be in a sealed cover super scribed "**TENDER FOR PROPOSED solar works.**"
9. The Contractor, whose tender is accepted, will be required to furnish by way of initial security deposit for the due fulfillment of his contract, such sum as will amount to **2.00%** of the estimated cost of work. The S.D. shall be collected as detailed in the general conditions of the contract. The EMD of the contractor, whose tender is accepted, shall be forfeited in full in case he does not remit the Initial Security Deposit within the stipulated period or start the work by the stipulated date mentioned in the award letter.
10. The acceptance of tender will rest with the State Bank of Bikaner & Jaipur which does not bind itself to accept the lowest tender, and reserves to itself, the authority to reject any or all of the tenders received without the assignment of a reason. All tenders in whom any

of the prescribed, conditions are not fulfilled or are incomplete in any respect are liable to be rejected.

The Bank reserves the right to accept the tender in full or in part and the tenderer shall have no claim for revision of rates or other conditions, if his tender is accepted in parts.

11. Canvassing in connection with tenders is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.
12. All rates shall be quoted on the proper form of the tender alone.
13. Tender containing any condition leading to unknown / indefinite liability, are liable to be summarily rejected. If at all any rebate(s) is/are to be offered the tenderer shall first quote his rates strictly on the terms and conditions stipulated in tender document and then show separately rebate(s) offered specifying the conditions for such rebate(s). Failure to follow this procedure will render the tender liable to summarily rejection.
14. All compensation or other sums of money payable by the Contractor to Clients under the terms of this contract may be deducted from the security deposit, or from any sum that may be or may become due to the Contractor on any account whatsoever and in the event of the Security Deposit being reduced by reasons of any such deductions, the Contractor shall within --- days of being asked to do make good in cash or by cheque any sum which have been deducted from his security deposit.
15. On acceptance of the tender, the name of the accredited representatives(s) of the contract or who would be responsible for taking instructions from the Employer/ shall be communicated to the Employer.
16. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only, in such a way that interpolation

is not possible. The total amount should be written both in figures and in words. In case of figures, the words "RS." should be written before the figures, e.g. Rs.2.15. and in case of word Rupees should precede and the word 'Paise' should be written at the end, unless the rate is in whole rupees and followed by the words 'only'. it should invariable be up to two decimal places. While quoting the rate is in schedule of quantities the word 'only' should be written closely following the amount and it should not be written in the next line.

17. Sales Tax or any other tax on material or on finished works like work's contract tax, Service Tax, Turn - over etc. in respect of this contract shall be payable by the contractor and the Bank will not entertain any claim whatsoever in this respect .
18. The contractor shall give a list of his relatives working with the Bank along with their designations and addresses.
19. No employee of the bank is allowed to work as a contractor for a period of two years of his retirement from Bank service, without the previous permission of the bank. This contract is liable to be cancelled if either the contractor or any of his employees is found at any time to be such a person who has not obtained the permission of the Bank as aforesaid before submission of the tender or engagement in the contractor's service.
20. The tender for works shall remain open for acceptance for a period of 90 (ninety) days from the date of opening of tenders. If any tenderer withdraws his tender before the said period, then the bank shall be at liberty to forfeit Earnest Money paid along with the tender.
21. The tender for the work shall not witness by a contractor or contractors who himself/themselves have/have tendered or who may and had/have tendered for the same work. Failure to observe this condition would render tenders of the contractors tendering as well as witnessing the tender liable to summary rejection.

22. It will be obligatory on the part of the tenderer to tender and sign the tender documents for all the component parts and that, after the work is awarded, he will have to enter into an agreement for each component with the competent authority in the bank.
23. The tender, apart from being a competent contractor must associate himself with agencies of the appropriate class who are eligible to tender for (i) electrical works.
24. The tenderer should visit the site to ascertain the working conditions and local authority regulations / restrictions if any and other information required for the proper execution of the work.
25. The quantities of various items given in the schedule of quantities are approximate. The quantities of work may vary at time of allotment / execution of work. Bank reserves the right to omit / delete any item(s) of work from the schedule at the time of allotment / before. Contractor will be paid for the actual work done at the site duly verified by the concerned official of the bank.
26. The unit price shall be deemed to be fixed price. In case of extra items, a record of labor charges paid shall be maintained and shall be presented regularly to the Employers for checking. The settlement will be made based on figures arrived at jointly and taking unit price given in the contract assigned to the successful Tenderer. In case of extra items where similar or comparable items are quoted in the tender, extra rates shall be based on tender rates.
27. If the rate quoted by the contractor for any item / items are not workable or abnormally lower than the market rate, the bank may demand Bank guarantee from the contractor for satisfactory completion of these work. The bank guarantee amount will be not less than 50% of the estimated amount of the items for which the rates are not workable or abnormally low. This bank guarantee will be released after

completion of these works (unworkable and abnormally low rated items) to the satisfaction of the bank.

28. No employee of the Bank is allowed to work as a contractor for a period of 2 years of his/her retirement from Bank Services without previous permission of the Bank. This contract is liable to be cancelled, if either the contractor or any of his employees is any time to be such a person who had not obtained the permission of Bank as aforesaid before submission of the tender or engagement in the contractor's service.
29. Sealed tenders in prescribed form in two envelopes (Envelope-1 should contain Earnest Money Deposit, in form of DD Drawn in favor of State bank of Bikaner & Jaipur, Jaipur, Payable at Jaipur, Tender Fee in form of DD of Rs.1000/- in favor of AGM Premises SBBJ HO . Payable at Jaipur, Pre-qualification forms, conditions of contract and technical specification. Envelope-2 should contain price bid. are to be addressed and sent to The Assistant General Manager, Premises, State bank of Bikaner & Jaipur, Head Office, Tilak Marg, Jaipur – 302005.
30. **Estimated Cost: Rs.4,00,000/-(Rs 4 Lakhs only)**

TECHNICAL DETAILS

TO supply, install, testing & commissioning of 5 KWp on grid Solar Power Plant at JN SriGanganagar Branch.

1. SPV MODULES:

Type and Quality

The total Solar PV Array Capacity shall be **5 KWp**. Mono/Poly Crystalline type solar modules of desired nominal voltage or peak power rating which meet specifications are considered appropriate for inclusion in this offer. Modules will be supplied by Vendor with a warranty that:

- Fabrication is in compliance with the standards approved by **MNRE/RRECL**.
- 250/300 Wp or any other higher capacity modules shall be used.
- Offered module shall have a power output warranty for 25 years.
- Solar cells / modules used have a proven record for the performance in actual field conditions of Rajasthan state. PV Modules have IEC 61215 certification.

The modules used shall have following specifications under STC:

Make	:(Standards approved by MNRE)
Type	:	250W60/300W72
Peak Power Output	:	250/300 Watts
Maximum Current	:	8.78 /8.78 A DC
Maximum Voltage	:	30/34 VDC
Dimension in mm	:	1658 x 997 x 42/ 1973 x 997 x 42
Type of Cell used	:	Mono/Poly Crystalline Silicon

2. MECHANICAL COMPONENTS

ARRAY SUPPORT STRUCTURE

Modules shall be mounted on a non-corrosive support structure suitable for site conditions. The inclination angle of the array support structure shall be in accordance with the latitude of the place of installation. No provision for adjusting inclination angle is required. There shall be mild steel frame structures (Hot dipped, Galvanized) for holding the PV modules to form the PV panels. Each panel frame structure shall be so fabricated as to be grouted using cement concrete foundation.

Each panel frame shall be complete with a weather proof junction box as per the relevant ISI specifications, where the module terminals shall be interconnected and output taken.

The panel frame structure be capable of with standing a wind load of 200 km per hour, after grouting and installation. The Structure has to be grouted on concrete Blocks complete in all respects and will be provided by the Vendor.

3. POWER CONDITIONER UNIT (PCU)

The power-conditioning unit will convert dc power produced by SPV array into AC power. The capacity of Centralized PCU shall be aggregate capacity of 5 KVA ON- grid single phase with communication system and data recording facility, digital display etc complete in all respects.

ELECTRICAL

INVERTER(FOR 5 KVA)	
Max. No. of Series panels	6-10 nos.
AC out put voltage	230 volt,1 phase, 50 Hz
Maximum out put capacity	5 KVA

Peak out put capacity	Up to 150% of maximum current for 15 seconds
Out put wave shape	Sine wave
THD	< 5 %
Max current ripple	4% peak to peak
No load power consumption	2.5 % of O/p rating
Efficiency at 30 degree centigrade	> 90%
ENVIRONMENTAL	
Cooling	Temperature controlled fan forced cooling
Ambient temperature range	0 deg to 55 deg
Ambient humidity range	5% to 90% condensing

Construction

The inverter(s) shall be supplied in IP 20 indoor enclosure.

Protections:

Following protections shall be provided:

- Short Circuit
- Overload
- Input surge voltage

5. ARRAY JUNCTION BOXES

The junction boxes shall be provided in PV array field for termination of connections from various arrays.

Features:

- Made of FRP

- Dust and vermin proof
- Suitable MOV's shall be provided for high voltage surge
- Copper bus bars of suitable rating

6. CABLES

Cabling will be carried out as per IE rules.

Cable Marking: All cables/wires shall be marked with good quality ferule for cable identification.

Cable Ends: All connections shall be made through suitable cable lugs/tags crimped properly and with the use of cable glands.

All cables shall be:-

- Multistrand , annealed high conductivity copper/aluminum conductor
- Overall PVC insulation for UV protection
- Armoured cables for under ground laying
- All cables shall conform to BIS standards

7. CIVIL WORK

Civil work shall include work related with foundation for installation of module mounting structures and other accessories. **However the Bank shall provide clear space for installation of SPV array and the control room for installation PCU.** The Vendor has to ensure the safety of of roof before installation and structural feasibility testing at his own cost, if required.

8. **Bidirectional Meter** :- The Vendor will arrange Bidirectional Meter(Digital) with recording facility and communication displays for the site to record the export of the energy produced. The installation will be done in consultation and liasioning with Authorities of State Electricity Distribution company and SBBJ and the export of Energy recorded will be displayed at the time of commissioning of the plant.

8. DANGER BOARDS AND SIGNALS

Danger boards should be provided as and where necessary.

9. LIGHTNING PROTECTION

The suitable lightning arrestors (ESE) installed in the array area. Lightning protection be provided by the use of metal oxide arrestors and suitable earthing such that induced transients find an alternate route to earth. Protection shall meet the safety rules as per Indian Electricity Act 2003/IE rules.

10. EARTHING PROTECTION

Each array structure of the PV yard be grounded/ earthed properly. In addition the lightning arrester/masts should also be provided inside the array field. Provision be kept for shorting and grounding of the PV array at the time of maintenance work. All metal casing/shielding of the plant be thoroughly grounded in accordance with Indian Electricity Act/IE Rules when required after earthing by calibrated earth tester. PCU and DCDB should also be earthed properly. Earth resistance is not more than 5 ohms. It will be ensured that all the earthing points are bonded together to make them at the same potential.

11. SURGE PROTECTION:

Internal surge protection are consist of three MOV type arrestors connected from +ve and – ve terminals to earth (via Y arrangement) for higher withstand of the continuous PV-DC voltage during earth fault condition. SPD have safe disconnection and short circuit interruption arrangements through integrated DC in-build bypass fuse (parallel) which get tripped during failure mode of MOV, extinguishing DC arc safely in order to protect the installation against fire hazards.

12. FIRE EXTINGUISHERS:

The fire fighting system for the proposed power plant for fire protection shall be consisting of:

- Portable fire extinguishers in the control room for fire caused by electrical short circuits.

The fire extinguishers shall be provided in the control room housing the PCU.

13. PROJECT DURATION

The work of supply & installation shall be completed within 1 month from the date of sanction of the project and clear order received from beneficiary

14. **WARRANTY of Array and PCU**:- Five years from date of supply against manufacturing defects only and 2 years onsite maintenance warranty complete in all respects with periodic 5 visits a year. However the defect liability period will be one year after which the SD amount will be released on submission of performance certificate by the Vendor.

15. **Service Centre**:- The Vendor should have a service centre in Sriganganagar/Bikaner/Jaipur from past 1 year of the Last date of submission of Tender documents. The complete address details are to be quoted for the aforesaid service centre with details of operating years. During first five years after commissioning, the Employee of the Vendor will visit the site within 1 hour at if asked for, during outages/maintenance problems of the plant.

FINANCIAL BID (TO BE SUBMITTED IN SEPARATE ENVELOPE)

Qty/Rate

The bill of material for 5 KWp Grid connected SPV Power Plant is as under:

Sr. No.	Description of item	Unit	Quantity	Rate	Amount (Rs)
1.	Solar PV Modules250/300 Wp	Set	5 KWp		
2.	Mounting Structure	Set	01 Set		
3.	Power Conditioning Unit (5 KVA)	Nos.	01No		
4.	Bidirectional Meter	1	01 Set		
5.	Array Junction Box	Set	01 set		
6.	Earthing Set	Set	01 set		
7.	Lightning Arrester	Set	01 Set		
8.	Wires and Cables	Set	As per site requirement		
9.	Installation accessories/tools	Set	01 set		
10.	Fire- Fighting Equipment	Set	01 Set		
11.	Danger and Sign Board	Set	01 Set		

Total

Terms & Conditions:

Price	:	FOR Site, Sriganaganagar including installation-commissioning
		Charges and two year warranty maintenance.
Validity of Offer	:	One month.
Delivery	:	within 7 days after clear techno-commercial order.
Warranty	:	Five years from date of supply against manufacturing Defects only and 2 years onsite maintenance warranty.

Scope of work:

(a) SBBJ, :

- Shall provide shadow free roof top area for installation of SPV On grid Power plant as per requirement,
- Shall arrange safe storage of material at respective site till commissioning of systems,
- provide covered space of Size **12 feet x 12 feet** for control room with proper ventilation, if required.

(b) VENDOR:

- VENDOR shall provide power (from SPV Power Plant) at one point only. CONTRACTOR scope of work includes site, survey, layout planning, design, development, Metering arrangements, Liasioning with JVVNL and RRECL authorities, if any and supply of all components of SPV System, Transportation of SPV Power system up to central location, I & C of SPV Power system, on site training of customer for routine visit maintenance for **2 years**.

The Vendor should possess the following documents and should submit the self attested copies of the following along with Technical bid:-

1. Certificate/License of approval from appropriate authority
2. PAN card in the name of the proprietor/firm/company
3. Service tax registration number
4. Income Tax Return for the Last three years
5. Work order and completion certificate/self certificate with similar work value and nature from at least two clients whose work has been undertaken in the last three years
6. Trade License or similar certificate.
7. Proof of service centre
8. The details of qualified staff

XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX

