

GOVERNMENT OF INDIA  
CENTRAL PUBLIC WORKS DEPARTMENT  
OFFICE Of The Assistant Executive Engineer (E) VCESD-I  
CPWD GPOA Office Complex, Autonagar, Vijayawada - 520 007  
E-mail: aeevjcesd1@gmail.com

NO:- 69(2)/2021/VCESD-I/241

Dated:- 11-10-2021.

**NOTICE INVITING QUOTATIONS**

The Assistant Executive Engineer(E),Vijayawada Central Electrical Sub Division I, Central P.W.D., 6th floor, CGO Complex, Auto Nagar, Vijayawada - 520 007( Telefax no.0866-2555781) invites sealed quotations from CPWD enlisted contractors on behalf of the President of India for the following work so as to reach his office up to 3.00 PM on 18/10/2021. The quotations will be opened at 3.30PM on the same day. The Envelop containing the quotation shall be superscribed with the name of work given below and due date of opening as 18/10/2021.

**Name of work:** C/o IT Services building for STPI at Vijayawada SH: Providing 60 kWp Grid Interactive roof top Solar Power plant on parking sheds and terrace of the building.SW: Providing suitable enclosure for equipment protection.

**SCHEDULE OF QUANTITIES**

SN	Description of Items	Qty	Unit	Rate	Amount
1	Fabrication, supply, installation of cubical Enclosure for the existing 60 KWP Inverter system of sizing not less than 2700x1800x1000 mm as a framed structure, with 32x32 mm medium duty hollow square bar for outer structure frame, 25x25 mm medium duty hollow square bar for door frames and closure of all faces with 5mm thick hylam sheet along with provision for opening on front side with locking arrangement including providing air vents for heat dissipation, painting of framed stucture complete as per the site requirement.	1	Job		
2	Fabrication, supply, installation of cubical Enclosure made up of 16 SWG CRCA sheet steel for housing Solar net metering equipment of size not less than 1200x1000x600 mm with provision of double leaf doors on front side, sloping towards sides on top surface complete with powder coating in approved shade and control wiring complete as required.	1	Job		
3	Providing of indication alarm system for providing buzzer sound upon restoartion of main supply after power failure including providing hooter,timer and control wiring complete as required.	1	Job		
<b>Total</b>					

**Terms and Conditions:**

- 1 Work shall be carried out at STPI, Vijayawada as directed by Engineer-in-charge. Work shall be carried out strictly as per relevant CPWD specifications.
- 2 The contractor shall make his own arrangements for all T&P required for the work and Transportaiton of Machinery.
- 3 Rate quoted shall be inclusive of GST. Statutory recoveries along with IT@2 % and Labour welfare cess @ 1 % shall be deducted at source from the payments to be made to the contractor. Advance payment will not be made.

4 Rate quoted shall be inclusive GST. Advance payment shall not be made.

5 The contractor is fully responsible to make his own arrangements for watch and ward of the materials at site as well as the installations provided by him till such time the installation/work is completed and handed over to the department in satisfactory working condition for which no extra claim will be entertained on account of damage, theft etc., for the materials and installation.

6 All the installations must be guaranteed for a period of 6 months from the date of installation.

7 Makes of Material: 1) FRLS Wires- Finelox, RR kabal, Polycab 2) MCB, Change over, selector switch and timer - Legrand, L&T, Schneider

// Contractor //

*Ajit*  
Assistant Executive Engineer (E)  
VCESD-I, CPWD, VJA-007

Copy to:

- 1 Notice Board
- 2 The Executive Engineer(E), TED, CPWD, Tirupathi.
- 3 The Junior Engineer (E), VCESD-I, CPWD, Vijayawada.
- 4 [www.tenderwizard.com](http://www.tenderwizard.com)

// Contractor //

*Ajit*  
Assistant Executive Engineer (E)