



Line Details Of Tender							
Srl. No.	Line Description	Ship To Location	UOM	Schedule Rate	HSN Code	Location GSTIN	Mandatory
Default schedule				Mandatory: Yes			
1	Sply & Inst MC4 connectors	11991-CHENNAI NEW TERMINAL	Each	50.8		33AAACH1118B1ZJ	Yes
2	Sply & lay of 6 Sqmm DC CBALE	11991-CHENNAI NEW TERMINAL	Each	62.7		33AAACH1118B1ZJ	Yes
3	Inverter repair (DC & AC Board	11991-CHENNAI NEW TERMINAL	Each	72033.9		33AAACH1118B1ZJ	Yes
DESCRIPTION => 25 KW - SMA - STP 25000TL-30							
4	Inverter repair (DC & AC Board	11991-CHENNAI NEW TERMINAL	Each	96610.2		33AAACH1118B1ZJ	Yes
DESCRIPTION => 50 KW - SMA - SOLID-Q50							
5	Inverter repair (DC & AC Board	11991-CHENNAI NEW TERMINAL	Each	56779.7		33AAACH1118B1ZJ	Yes
DESCRIPTION => 30 KW - DELTA- RPI-M30A							
6	Inverter repair (DC & AC Board	11991-CHENNAI NEW TERMINAL	Each	42372.9		33AAACH1118B1ZJ	Yes
DESCRIPTION => 15 KW - DELTA- RPI-M15A							
7	Sply & Ins of 25KW Inverter	11991-CHENNAI NEW TERMINAL	Each	186440.7		33AAACH1118B1ZJ	Yes
DESCRIPTION => Approved makes: Delta/Havells/SMA/Growatt							
8	Sply & Ins of 50KW Inverter	11991-CHENNAI NEW TERMINAL	Each	347457.6		33AAACH1118B1ZJ	Yes
DESCRIPTION => Approved makes: Delta/Havells/SMA/Growatt							
9	Sply & Ins of 30KW Inverter	11991-CHENNAI NEW TERMINAL	Each	194915.3		33AAACH1118B1ZJ	Yes
DESCRIPTION => Approved makes: Delta/Havells/SMA/Growatt							
10	Sply & Ins of 15KW Inverter	11991-CHENNAI NEW TERMINAL	Each	152542.4		33AAACH1118B1ZJ	Yes
DESCRIPTION => Approved makes: Delta/Havells/SMA/Growatt							
11	Sply & Ins of DC compiler box	11991-CHENNAI NEW TERMINAL	Each	12711.9		33AAACH1118B1ZJ	Yes
DESCRIPTION => 5in 5out IP65 rated with SPD with fuse and MCB							
12	Sply & Inst of PV module	11991-CHENNAI NEW TERMINAL	Each	38.1		33AAACH1118B1ZJ	Yes
DESCRIPTION => Unit Each = Watt. This requires replacement of PV module with new module.							
13	Weekly watering of solar plant	11991-CHENNAI NEW TERMINAL	Each	3813.6		33AAACH1118B1ZJ	Yes
DESCRIPTION => Weekly watering of solar plants							
14	Monthly health checkup	11991-CHENNAI NEW TERMINAL	Each	12711.9		33AAACH1118B1ZJ	Yes
DESCRIPTION => 3 DAYS VISIT MINIMUM is required. Any penalty due to less production will be recovered from this line item also.							
15	PCC 1:2:4	11991-CHENNAI NEW TERMINAL	Each	6101.6		33AAACH1118B1ZJ	Yes
16	SPLY & LAYG OF ARMoured CABLE	11991-CHENNAI NEW TERMINAL	Meters	677.97	995423	33AAACH1118B1ZJ	Yes
DESCRIPTION => SUPPLY AND LAYING OF 3.5C X 70 SQ.MM ALUMINIUM ARMoured XLPE CABLE: ALUMINIUM ARMoured XLPE CABLE (FOR EXTENSION OF EXISTING CABLES IF REQUIRED) AS PER TECHNICAL SPECIFICATION. EXECUTION OF LINE ITEM WILL DEPEND ON SITE CONDITION AND REQUIREMENT.							
17	SPLY AND INSTLN CABLE TRAY	11991-CHENNAI NEW TERMINAL	Meters	762.7	995423	33AAACH1118B1ZJ	Yes
DESCRIPTION => SUPPLY, ERECTION/INSTALLATION/MOUNTING OF 1.5 MM THK AND 150 MM WIDE AND 25 MM HEIGHT PERFORATED GI CABLE TRAY INCLUSIVE OF CABLE BINDING WITH SUITABLE GI CLAMPS, GI HOOKS, GI NUTS AND BOLTS COMPLETE IN THE TRAY IN A NEAT WAY. THE WIDTH SPECIFIED SHALL BE OF CABLE MOUNTING AREA. BENDS AT BOTH THE SIDES OF CABLE TRAY SHALL BE IN ADDITION TO IT. WITHOUT BINDING							
18	SPLY & FAB OF STRUCTURAL STEEL	11991-CHENNAI NEW TERMINAL	Kilograms	296.61	995455	33AAACH1118B1ZJ	Yes
DESCRIPTION => SUPPLY AND FABRICATION OF STRUCTURAL STEEL TUBE WITH HOT DIP GALVANIZED IRON.SUPPLYING, CLEANING, STRAIGHTENING, BENDING IF REQUIRED, FABRICATION AND FIXING OF STRUCTURAL STEEL TUBE WITH HOT DIP GALVANIZED IRON. ALL THE MATERIAL ALONG WITH ACCESSORIES ARE TO BE SUPPLIED BY CONTRACTOR. JOB INCLUDES CARRYING OUT ANY KIND OF CIVIL WORK THAT REQUIRES IN ORDER TO EXECUTE THE JOB.							