

कार्यालय नगर परिषद नागभीड
ता. नागभीड जि. चंद्रपुर

जा.क्र.न.प./पा.पु.विभाग/1750/2022

दि 07/10/2022.

* ई-निविदा सूचना*



नागभीड नगर परिषद जिल्हा चंद्रपुर खालील कामाच्या अंदाजपत्रक तयार करण्याकरिता ई-निविदा पध्दतीने ईच्छुक कंत्राटदाराकडून खाली दिलेल्या विवरणानुसार दर निविदा मागविण्यात येत आहे. खालील कामाच्या निविदा केवळ ई-निविदा पध्दतीने सादर करावयाचे आहे. निविदेचा विस्तृत नमुना महाराष्ट्र शासनाच्या <http://mahatenders.gov.in> या संकेतस्थळावर प्रसिध्द करण्यात आल्या असून दिनांक ०७/१०/२०२२ पासून पहावयास व भरावयास उपलब्ध आहे. करावयाच्या कामाचा तपशिल खालील प्रमाणे.

अ. क्र.	कामाचे विवरण	इसारा रक्कम	निविदा प्रपत्र किंमत	कामाचा कालावधी
1	Supplying installing Testing and Commissioning of 250 kwp On GRID Solar PV system /Plant consisting solar pv poly Crystalline panel (335wp X 300Nos)and Solar ON Ground Inverter of Similar Capicity (THD<%)With Interconnecting wires /Cabel up to solar on GRID inverter Proper base plate Canopy box to house Inverter and Necessary accessorices i.e.ACDB /DCBD MICB etc wiring up to solar inverter in casing and capping display Board sign Board two distinct earthing lightning arrester liaisoning charges Remote Monitoring System With Maintaining card/Chip For 5 years Including net charges for RMS System Complate up to net meter installing and export to the Grid With 5 Year ON -SITE Warranty and Fully Compehensive Maintenance Contract as Per Specification no.ESD -RT-ONG.			
2.	Supplying installing Testing and Commissioning of 300 kwp On GRID Solar PV system /Plant consisting solar pv poly Crystalline panel (335wp X 300Nos)and Solar ON Ground Inverter of Similar Capicity (THD<%)With Interconnecting wires /Cabel up to solar on GRID inverter Proper base plate Canopy box to house Inverter and Necessary accessorices i.e.ACDB /DCBD MICB etc wiring up to solar inverter in casing and capping display Board sign Board two distinct earthing lightning arrester liaisoning charges Remote Monitoring System With Maintaining card/Chip For 5 years Including net charges for RMS System Complate up to net meter installing and export to the Grid With 5 Year ON -SITE Warranty and Fully Compehensive Maintenance Contract as Per Specification no.ESD -RT-ONG			
3.	Supplying Installing Testing and Commissioning of 350 kwp On GRID Solar PV system /Plant consisting solar pv poly Crystalline panel (335wp X 300Nos)and Solar ON Ground Inverter of Similar Capicity (THD<%)With			